

ELEVATION	(ft)	178.63	181.03	185.46	187.40	189.48	191.99	193.90	193.78	190.88	188.83	188.21	186.43
DISTANCE	(ft)	0.00	5.78	23.88	34.98	42.33	51.63	58.76	73.09	78.88	86.34	92.56	99.47

CROSS SECTION


Distance(ft)	X	Y
99.47	448734.64	3069485.56
92.56	448736.18	3069484.12
86.34	448737.34	3069482.61
78.88	448738.77	3069480.83
73.09	448740.02	3069479.58
58.76	448743.00	3069476.39
51.63	448744.65	3069474.96
42.33	448746.45	3069472.75
34.98	448748.04	3069471.17
23.88	448750.26	3069468.59
5.78	448754.50	3069465.03
0.00	448755.62	3069463.68

LEGEND:

STONE PICHING



COMPACTED FILL



CRS: UTM42N

NOTE:
THE HFL HAS BEEN ESTIMATED BASED ON THE SINDH BUND MANUAL
AND IS YET TO BE VALIDATED BY HISTORIC OBSERVATION.

SHEET 5

CLIENT:



IRRIGATION DEPARTMENT
GOVERNMENT OF SINDH



SINDH RESILIENCE PROJECT
SINDH IRRIGATION DEPARTMENT

							DRAWN	AA
							CHECKED	
							RECOMMENDED	
REV.	DATE	DESCRIPTION	BY	CKD.	APPR.	APPROVED		

IRRIGATION DEPARTMENT
SUKKUR LARKANA BUND MILE 14-6 TO 30-3
Sukkur Larkana Bund 10/2

DATE	DWG. NO.	REV.
MARCH, 2023	SRP/Sukkur Larkana Bund/CS/05	0